SURENOO GRAPHIC OLED SERIES DISPLAY
Product Specification

Part Name: OEL Display Panel
SOG12832B4_P091

Please click the following image to buy the sample

Surenoo 0.91"-128*32 Graphic OLED Panel
Model No.: SOG12832B4-P091 (15P/0.3)

Surenoo Display

Business Card | WhatsAPP | 카카오톡 | LINE (ライン) | WeChat

Shenzhen Surenoo Technology Co.,Ltd.
www.surenoo.com
E-mail: info@surenoo.com

Graphic OLED Display Selection Guide

Graphic OLED Module | Graphic OLED Panel

SSD1306

CONTENTS

RECORDS OF REVISION

DATE	REVISED NO.	REVISED DESCRIPTIONS	PREPARED	CHECKED	APPROVED
09.30.2017	VER1.0	FIRST ISSUE			

3. GENERAL SPECIFICATIONS：

3-1 SCOPE:

This specification covers the delivery requirements for the organic light emitting diode display delivered by quality to Customer.

3-2 PRODUCTS:

Organic light emitting diode (OLED)

3-3 MODULE NAME:

P12832-04-W15P091

4. FEATURES：

(1) Display Color:　WHITE

(2) Dot Matrix:　　128x32

(3) Drive IC:　　　SSD1306BZ

(4) Viewing Angle:　160°

(5) Aperture rate:　82.5%

(6) Interface:　　　4 wire serial interface

5. MACHANICAL SPECIFICATIONS：

ITEM	SPECIFICATIONS UNIT	
MODULE SIZE	30.0(W)x11.5(H)x1.227(D)	mm
VIEWING AREA	24.384 (W) x 7.584(H)	mm
ACTIVE AREA	22.384 (W) x5.584(H)	mm
DOT SIZE	0.159(W) x0.159(H)	mm
DOT PITCH	0.175(W) x0.175 (H)	mm
ASSY.TYPE	COG	---
WEIGHT	TBD	

NOTES:

OLED should be grounded during handling OLED.

SHENZHEN SURENOO TECHNOLOGY CO.,LTD.

1.4 Mechanical Drawing

www.surenoo.com

Item	Date	Remark
A	20190425	Original Drawing

30±0.2

18±0.2

26.6±0.2

3.2±0.2

0.3

26±0.3(Polarizer)

2.2±0.2

1.1

24.384(V/A)

0.65

2.1

22.384(A/A)

0.65

PULL TAPE 15*5MM(RED)

128*32 DOTS 0.91''

Single Tape

3.35

2.4

0.3

0.3±0.05

0.1±0.05

4.8±0.05

P0.3*(15-1)=4.2±0.05

4±0.1 4±0.2

0.8±0.08

0.3

11.5±0.2

10.5±0.3(Polarizer)

7.584(V/A)

5.584(A/A)

0.5

1.1

2.1

P0.175x128-0.016=22.384

"A"

Segment 127 (Column 1)

Segment 0 (Column 128)

Common 0 (Row 32)

Common 31 (Row 1)

P0.175x32-0.016=5.584

0.175

0.159

0.159

0.175

Detail "A" Scale (10:1)

1.227±0.15 (w/o handler)

0.207(Polarizer)

0.5

1.5MAX (seal,Black)

3.4MAX (seal cover IC,Black)

Stiffener

Contact side

0.2±0.05

Specifications:
1. Display : OLED(BLUE/WHITE).
2. Dot Matrix: 128*32
3. Dot Size: 0.159*0.159mm
4. Dot Pitch: 0.175*0.175mm
5. Aperture Rate: 82.5%
6. Active Area : 22.384*5.584mm
7. Drive IC: SSD1306BZ
8. FPC P/N: FPC-HP12832-04-A0

PIN	SYMBOL
1	C2P
2	C2N
3	C1P
4	C1N
5	VBAT
6	VSS
7	VDD
8	CS#
9	RES#
10	D/C#
11	SCLK
12	SDIN
13	IREF
14	VCOMH
15	VCC

Customer Approval Signature

SHENZHEN SURENOO TECHNOLOGY CO.,LTD.

SOG12832B4-P091 Folding Type OEL Display Module
Pixel Number: 128x32, Monochrome, COG Package

Drawing Number

Re A

Material

Soda Lime / Polyimide

Unless Otherwise Specified		Title					
Unit	mm						
General Roughness							
Tolerance		Drawn	E.E.	Panel / E.	P.M.		
Dimension	±0.3	By	HBK			Scale	Sheet	Size
Angle	±1	Date	20190425			1:1	1 of 1	A4

Surenoo Display

7. INERFACE SPECIFICATIONS

7-1. PIN ASSIGNMENT

PIN NO.	SYMBOL	TYPE	FUNCTION DESCRIPTIONS
1	C2P	I	C1P/C1N-Pin for charge pump capacitor.
2	C2N		C2P/C2N-Pin for charge pump capacitor.
3	C1P		Connect to each other with a capacitor. They must be floated when the
4	C1N		Charge pump not use.
5	VBAT	P	Power supply for charge pump regulator circuit. It must be connected to external source when charge pump is used. It must be float when charge pump is not used.
6	VSS	P	Ground pin. It must be connected to external ground.
7	VDD	P	Power pin for logic circuit. It must be connected to external source.
8	CS#	I	Chip Select input pin. Active "L"
9	RES#	I	Hardware reset input pin. Active "L".
10	DC#	I	This is Data/Command control pin. When the pin is pulled HIGH, the data at D[7:0] is data. When the pin is pulled LOW, the data at D[7:0] is command.
11	SCLK	I	4 wire serial interface clock wire
12	SDIN	I	4 wire serial interface data wire
13	IREF	I	Current reference for brightness adjustment. This is segment output current reference pin. A resistor should be connected between this pin and VSS .Set the current at 12.5 uA maximum.
14	VCOMH	O	COM signal deselected voltage level. A capacitor should be connected between this pin and VSS.
15	VCC	P	Power supply for OLED driving voltage. A capacitor should be connected between this pin and VSS, when charge pump is used. It must be connected to external source when charge pump is not used.

7-2 APPLICATION CIRCUIT

7-2-1 4 Wire Serial Interface With Internal Charge Pump

特别提醒(Special Tips):主板设计务必加电子开关，否则，可能引起漏电流现象

(When design main board, Please add Electronic Switch circuit, otherwise, will be caused leak current)

4SPI INTERFACE

SYMBOL	PIN
C2P	1
C2N	2
C1P	3
C1N	4
VBAT	5
VSS	6
VDD	7
CS#	8
RES#	9
D/C#	10
SCLK	11
SDIN	12
IREF	13
VCOMH	14
VCC	15

Recommended Components:

C1, C2:	1μF / 16V, X5R
C3, C4:	1μF / 16V, X5R
C5,C6:	4.7μF / 25V,X7R
R1:	560kΩ, R1 = (Voltage at IREF - VSS) / IREF
R2, R3:	47kΩ
Q1:	FDN338P
Q2:	FDN335N

Notes:

VDD: 1.65~3.3V, it should be equal to MPU I/O voltage.

Vin: 3.5~4.2V

* VBAT will be connected to VDD when VCC be connected to external source (9V), R1 should be replaced as 560 **kΩ**.

8. ABSOLUTE MAXIMUM RATING

Characteristic	Symbol	Standard Value			Unit	Notes
		MIN	TYP	MAX		
Power Supply Voltage(1)	V_{DD}	-0.3	-	+4.0	V	1,2
Power Supply Voltage(2)	V_{BAT}	-0.3	-	4.5	V	1,2
Power Supply Voltage(3)	V_{CC}	0	-	15.0	V	1,2
Operating Temperature	T_{OPR}	-40	-	+70	^0C	
Storage Temperature	T_{STG}	-40	-	+85	^0C	3
Life Time (120 cd/m^2)		10000	-	-	hour	4
Life Time (80 cd/m^2)		30000	-	-	hour	4
Life Time (60 cd/m^2)		50000	-	-	hour	4

Note 1: All the above voltages are on the basis of "V_{SS} = 0V".

Note 2: When this module is used beyond the above absolute maximum ratings, permanent breakage of the module may occur. Also, for normal operations, it is desirable to use this module under the conditions according to Section 9-1 "DC ELECTRICAL CHARACTERISTICS". If this module is used beyond these conditions, malfunctioning of the module can occur and the reliability of the module may deteriorate.

Note 3: The defined temperature ranges do not include the polarizer. The maximum withstood temperature of the polarizer should be 80°C.

Note 4: V_{CC} = 9.0V, T_a = 25°C, 50% Checkerboard.
End of lifetime is specified as 50% of initial brightness reached. The average operating lifetime at room temperature is estimated by the accelerated operation at high temperature conditions.

9.ELECTRICAL CHARACTERISTICS

9-1 DC ELECTRICAL CHARACTERISTICS

Symbol	Parameter	Test condition	Standard Value			Unit
			MIN	TYP	MAX	
V_{DD}	Logic Supply Voltage	-	1.65	2.8	3.3	V
V_{BAT}	Charge Pump Regulator Supply Voltage	Internal Charge Pump Enable	3.5	-	4.2	V
V_{CC}	Operating Voltage for OLED (Generated by charge pump)	Internal Charge Pump Enable	7.0	7.5		V
V_{CC}	Operating Voltage for OLED (Supplied Externally)	Internal Charge Pump Disable	8.5	9.0	9.5	V
V_{IH}	High Logic Input Level		$0.8*V_{DD}$	-	-	V
V_{IL}	Low Logic Input Level		-	-	$0.2*V_{DD}$	V
V_{OH}	High Logic Output Level	I_{OUT} = 100µA, 3.3MHz	$0.9*V_{DD}$	-	-	V
V_{OL}	Low Logic Output Level	I_{OUT} = 100µA, 3.3MHz	-	-	$0.1*V_{DD}$	V
$I_{DD, SLEEP}$	$I_{DD,}$ Sleep Mode Current		-	-	10	uA
$I_{BAT, SLEEP}$	$I_{BAT,}$ Sleep Mode Current		-	-	10	uA
$I_{CC, SLEEP}$	$I_{CC,}$ Sleep Mode Current		-	-	10	uA
I_{DD}	V_{DD} Supply Current		-	50	150	uA
I_{CC}	V_{CC} Supply Current (V_{CC} Supplied Externally)	V_{DD} = 2.8V, V_{CC} = 9V, 100% Display Area Turn on	-	9.0	15.0	mA
I_{BAT}	I_{BAT} Supply Current (V_{CC} Generated by charge pump)	V_{DD} = 2.8V, V_{CC} = 7.25V, 100% Display Area Turn on	-	17.5	19.5	mA

9-2 ELECTRO-OPTICAL CHARACTERISTICS

| Symbol	Parameter	condition	Standard Value			Unit
			MIN	TYP	MAX	
L_{br}	Brightness (V_{CC} Supplied Externally)		120	-	-	cd/m^2
L_{br}	Brightness (V_{CC} Generated by charge pump)		110	130	-	cd/m^2
(x)	C.I.E. (White)	C.I.E. 1931	0.25	0.29	0.33	
(y)			0.27	0.31	0.35	
CR	Dark Room Contrast		-	2000:1	-	
	Viewing Angle		-	160	-	degree

* Optical measurement taken at V_{DD} = 2.8V, V_{CC} = 9V & *7.25V*.

9-3 AC ELECTRICAL CHARACTERISTICS

9-3-1 4-Wire Serial Interface Timing Characteristics

$(V_{DD} - V_{SS} = 1.65V$ to $3.3V$, $T_A = 25°C)$

Symbol	Parameter	Min	Typ	Max	Unit
t_{cycle}	Clock Cycle Time	100	-	-	ns
t_{AS}	Address Setup Time	15	-	-	ns
t_{AH}	Address Hold Time	15	-	-	ns
t_{CSS}	Chip Select Setup Time	20	-	-	ns
t_{CSH}	Chip Select Hold Time	10	-	-	ns
t_{DSW}	Write Data Setup Time	15	-	-	ns
t_{DHW}	Write Data Hold Time	15	-	-	ns
t_{CLKL}	Clock Low Time	20	-	-	ns
t_{CLKH}	Clock High Time	20	-	-	ns
t_R	Rise Time	-	-	40	ns
t_F	Fall Time	-	-	40	ns

10. FUNCTIONNAL SPECIFICATIONS

10-1 COMMANDS

Refer to the SSD1306 IC Spec.

10-2 POWER UP AND POWER DOWN SEQUENCE

To protect OEL panel and extend the panel life time, the driver IC power up/down routine should include a delay period between high voltage and low voltage power sources during turn on/off. It gives the OEL panel enough time to complete the action of charge and discharge before/after the operation.

10-2-1 Power up Sequence:

1. Power up V_{DD} / V_{BAT}
2. Send Display off command
3. Initialization
4. Clear Screen
5. Power up V_{CC}
6. Delay 100ms
   (When V_{CC} is stable)
7. Send Display on command

10-2-2 Power down Sequence:

1. Send Display off command
2. Power down V_{CC} / V_{BAT}
3. Delay 100ms
   (When V_{CC} / V_{BAT} is reach 0 and panel is completely discharges)
4. Power down V_{DD}

Note:

1) Since an ESD protection circuit is connected between V_{DD} and V_{CC} inside the driver IC, V_{CC} becomes lower than V_{DD} whenever V_{DD} is ON and V_{CC} is OFF.
2) V_{CC} / V_{BAT} should be kept float (disable) when it is OFF.
3) Power Pins (V_{DD}, V_{CC}, V_{BAT}) can never be pulled to ground under any circumstance.
4) V_{DD} should not be power down before V_{CC} / V_{BAT} power down.

10-3 Reset Circuit

When RES# input is low, the chip is initialized with the following status:

1. Display is OFF
2. 128×64 Display Mode
3. Normal segment and display data column and row address mapping (SEG0 mapped to column address 00h and COM0 mapped to row address 00h)
4. Shift register data clear in serial interface
5. Display start line is set at display RAM address 0
6. Column address counter is set at 0
7. Normal scan direction of the COM outputs
8. Contrast control register is set at 7Fh
9. Normal display mode (Equivalent to A4h command)

10-4 Actual Application Example

Command usage and explanation of an actual example . VCC generated by charge pump.

<Power up Sequence>

V_{DD}/V_{BAT} off State	Set Multiplex Ratio 0xA8, 0x3F	Set Entire Display On/Off 0xA4
Power up V_{DD} (RES# as Low State)	Set Display Offset 0xD3, 0x00	Set Normal/Inverse Display 0xA6
Power Stabilized (Delay Recommended)	Set Display Start Line 0x40	*Clear Screen*
Power up V_{DDB} (100ms Delay Recommended)	Set Segment Re-Map 0xA1	Set Charge Pump 0x8D, *0x14*
Set RES# as High (3µs Delay Minimum)	Set COM Output Scan Direction 0xC8	Set Display On 0xAF
Initialized State (Parameters as Default)	Set COM Pins Hardware Configuration 0xDA, 0x12	Power Stabilized (100ms Delay Recommended)
Set Display Off 0xAE	Set Contrast Control 0x81, 0xB0	*Display Data Sent*
Initial Settings Configuration	Set Pre-Charge Period 0xD9, 0x22	
Set Display Clock Divide Ratio/Oscillator Frequency 0xD5, 0x90	Set VCOMH Deselect Level 0xDB, 0x30	

*If the noise is accidentally occurred at the displaying window during the operation, please reset the display in order to recover the display function.

<Power down Sequence>

```
┌─────────────────────┐         ┌─────────────────────────┐         ┌─────────────────────────┐
│  Normal Operation   │         │    Power Stabilized     │         │  V_DD/V_BAT off State   │
└─────────────────────┘         │ (100ms Delay Recommended)│         └─────────────────────────┘
          │                     └─────────────────────────┘
          ▼                                  ▼
┌─────────────────────┐         ┌─────────────────────────┐
│   Set Display Off    │         │     Power down V_BAT     │
│        0xAE          │         │ (50ms Delay Recommended) │
└─────────────────────┘         └─────────────────────────┘
          │                                  ▼
          ▼                     ┌─────────────────────────┐
┌─────────────────────┐         │     Power down V_DD      │
│   Set Charge Pump    │         └─────────────────────────┘
│     0x8D, 0x10       │
└─────────────────────┘
```

<Entering Sleep Mode>

```
┌─────────────────────┐         ┌─────────────────────────┐         ┌─────────────────────────┐
│  Normal Operation   │         │     Set Charge Pump      │         │      Sleep Mode         │
└─────────────────────┘         │       0x8D, 0x10         │         └─────────────────────────┘
          │                     └─────────────────────────┘
          ▼                                  ▼
┌─────────────────────┐         ┌─────────────────────────┐
│   Set Display Off    │         │     Power down V_BAT     │
│        0xAE          │         └─────────────────────────┘
└─────────────────────┘
```

<Exiting Sleep Mode>

```
┌─────────────────────┐         ┌─────────────────────────┐         ┌─────────────────────────┐
│     Sleep Mode      │         │     Set Charge Pump      │         │    Power Stabilized     │
└─────────────────────┘         │       0x8D, 0x14         │         │ (100ms Delay Recommended)│
          │                     └─────────────────────────┘         └─────────────────────────┘
          ▼                                  ▼                                  ▼
┌─────────────────────┐         ┌─────────────────────────┐         ┌─────────────────────────┐
│    Power up V_BAT    │         │     Set Display On       │         │   Normal Operation      │
│(100ms Delay Recommended)│      │         0xAF            │         └─────────────────────────┘
└─────────────────────┘         └─────────────────────────┘
```

```
void Init_Lcd(void)
{
    RST=1;
    Delay_1ms(100);
    RST=0;
    Delay_1ms(100);
    RST=1;
    Delay_1ms(100);

    Write_Command(0xAE);//set display display ON/OFF,AFH/AEH

    Write_Command(0x40);//set display start line:COM0

    Write_Command(0x20);//set memory addressing mode
    Write_Command(0x02);//page addressing mode

    Write_Command(0x81);//set contrast control
    Write_Command(0x8F);

    Write_Command(0xA0);//set segment re-map

    Write_Command(0xA4);//entire display on: A4H:OFF/A5H:ON

    Write_Command(0xA6);//set normal/inverse display: A6H:normal/A7H:inverse

    Write_Command(0xA8);//set multiplex ratio
    Write_Command(0x1F);//32

    Write_Command(0xC0);//set com output scan direction

    Write_Command(0xD3);//set display    offset
    Write_Command(0x00);//

    Write_Command(0xDA);//set seg pins hardware configuration
    Write_Command(0x02);//

    Write_Command(0xD5);//set display    clock divide ratio/oscillator frequency
    Write_Command(0x80);//FR=105HZ

    Write_Command(0xD9);//set pre-charge period
    Write_Command(0x1F);//

    Write_Command(0xDB);//set vcomh deselect level
    Write_Command(0x30);//0.83*VCC
```

```
Write_Command(0x8D);//charge pump setting
Write_Command(0x14);//enable charge pump, select 7.5V charge pump output
Delay_1ms(100);


Write_Command(0xAF);//set display display ON/OFF,AFH/AEH



}
void Write_Command (Uchar Command)
{
    int i;
    CS=0;
    A0=0;
    for(i=0;i<8;i++)
     {
       SCLK=0;
       if((Command&0x80)==0)
          SDA=0;
       else
          SDA=1;
       SCLK=1;
       Command=Command<<1;
     }
    CS=1;
 }
void Write_Data (Uchar Data)
{
    int i;
    CS=0;
    A0=1;
    for(i=0;i<8;i++)
     {
       SCLK=0;
       if((Data&0x80)==0)
          SDA=0;
       else
          SDA=1;
       SCLK=1;
       Data=Data<<1;
     }
    CS=1;
}
```

11.　RELIABILITY

ITEM	CONDITIONS	CRITERION
OPERATING TEMPERATURE	HIGH TEMPERTURE +70℃ 240HRS	NO DEFECT IN DISPLAYING AND OPERATIONAL FUNCTION
	LOW TEMPERTURE -40℃ 240HRS	
STORAGE TEMPERATURE	HIGH TEMPERTURE +85℃ 240HRS	NO DEFECT IN DISPLAYING AND OPERATIONAL FUNCTION
	LOW TEMPERTURE - 40℃ 240HRS	
HUMIDITY	60℃ 90%RH 120HRS	NO DEFECT IN DISPLAYING AND OPERATIONAL FUNCTION
VIBRATION	• Operating Time: thirty minutes exposure for each direction (X,Y,Z) • Sweep Frequency: 10～55Hz (1 min) • Amplitude: 1.5mm	NO DEFECT IN DISPLAYING AND OPERATIONAL FUNCTION
THERMAL SHOCK	-40℃(60mins)←→+85℃(60mins), 24 cycles	NO DEFECT IN DISPLAYING AND OPERATIONAL FUNCTION

*NOTE: TEST CONDITION

(1)TEMPERATURE AND HUMIDITY: IF NO SPECIFICATION, TEMP. SET AT 25±2℃, HUMIDITY SET AT 60±5%RH

(2) OPERATING STATE: SAMPLES SUBJECT TO THE TESTS SHALL BE IN " OPERATING" CONDITION

12. Outgoing Quality Control Specifications

12.1 Environment Required

Customer's test & measurement are required to be conducted under the following conditions:

Temperature:	$23 \pm 5°C$
Humidity:	$55 \pm 15\%$ RH
Fluorescent Lamp:	30W
Distance between the Panel & Lamp:	≥ 50cm
Distance between the Panel & Eyes of the Inspector:	≥ 30cm

Finger glove (or finger cover) must be worn by the inspector.

Inspection table or jig must be anti-electrostatic.

12.2 Sampling Plan

Level II, Normal Inspection, Single Sampling, MIL-STD-105E

12.3 Criteria & Acceptable Quality Level

Partition	AQL	Definition
Major	0.65	Defects in Pattern Check (Display On)
Minor	1.0	Defects in Cosmetic Check (Display Off)

12.3.1 Cosmetic Check (Display Off) in Non-Active Area

Check Item	Classification	Criteria
Panel General Chipping	Minor	X > 6 mm (Along with Edge) Y > 1 mm (Perpendicular to edge)

12.3.1 Cosmetic Check (Display Off) in Non-Active Area (Continued)

Check Item	Classification	Criteria
Panel Crack	Minor	Any crack is not allowable.
Copper Exposed (Even Pin or Film)	Minor	Not Allowable by Naked Eye Inspection
Film or Trace Damage	Minor	
Terminal Lead Prober Mark	Acceptable	
Glue or Contamination on Pin (Couldn't Be Removed by Alcohol)	Minor	
Ink Marking on Back Side of panel (Exclude on Film)	Acceptable	Ignore for Any

12.3.2 Cosmetic Check (Display Off) in Active Area

It is recommended to execute in clear room environment (class 10k) if actual in necessary.

Check Item	Classification	Criteria
Any Dirt & Scratch on Polarizer's Protective Film	Acceptable	Ignore for not Affect the Polarizer

Scratches, Fiber, Line-Shape Defect (On Polarizer)	Minor	W ≤ 0.1 Ignore
		W > 0.1
		  L ≤ 2 n ≤ 1
		  L > 2 n = 0

Dirt, Black Spot, Foreign Material, (On Polarizer)	Minor	Φ ≤ 0.1 Ignore 0.1 < Φ ≤ 0.25 n ≤ 1 0.25 < Φ n = 0
Dent, Bubbles, White spot (Any Transparent Spot on Polarizer)	Minor	Φ ≤ 0.5 ➜ Ignore if no Influence on Display 0.5 < Φ n = 0
Fingerprint, Flow Mark (On Polarizer)	Minor	Not Allowable

*   Protective film should not be tear off when cosmetic check.

**   Definition of W & L & Φ (Unit: mm): Φ = (a + b) / 2

12.3.3 Pattern Check (Display On) in Active Area

Check Item	Classification	Criteria
No Display	Major	
Missing Line	Major	
Pixel Short	Major	
Darker Pixel	Major	
Wrong Display	Major	
Un-uniform	Major	

13. Package Specifications

EPE COVER FOAM 351x212x1,
ANTISTATIC x 1 Pcs

Module

Tray 420x285 T=0.8mm

x 1 pcs (Empty)

x 15 pcs

Staggered Stacking

A

Exsiccator x 2 pcs

Wrapped with adhesive tape
x 16 pcs

B

Vacuum packing bag

EPE PROTECTTIVE
370mm x 280mm x 20mm

Primary L450mm x W296 x H110, B wave
x 4Pcs

Label

C

Carton Box L464mm x W313mm x H472mm, AB wave

B

16 Pcs Tray Vacuum packing

EPE PROTECTTIVE

Brimary Box 4 SET

CARTON BOX

Label

| Univision Technology Inc. |
| Part ID : |
| Lot ID : |
| Q'ty : |
| QC : |

Item		Quantity	
Module		**810**	**per Primary Box**
Holding Trays	**(A)**	**15**	**per Primary Box**
Total Trays	**(B)**	**16**	**per Primary Box (Including 1 Empty Tray)**
Primary Box	**(C)**	**1~4**	**per Carton (4 as Major / Maximum)**

14. Precautions When Using These OEL Display Modules

14.1 Handling Precautions

1) Since the display panel is being made of glass, do not apply mechanical impacts such us dropping from a high position.

2) If the display panel is broken by some accident and the internal organic substance leaks out, be careful not to inhale nor lick the organic substance.

3) If pressure is applied to the display surface or its neighborhood of the OEL display module, the cell structure may be damaged and be careful not to apply pressure to these sections.

4) The polarizer covering the surface of the OEL display module is soft and easily scratched.   Please be careful when handling the OEL display module.

5) When the surface of the polarizer of the OEL display module has soil, clean the surface.   It takes advantage of by using following adhesion tape.

   *   Scotch Mending Tape No. 810 or an equivalent

    Never try to breathe upon the soiled surface nor wipe the surface using cloth containing solvent such as ethyl alcohol, since the surface of the polarize will become cloudy.

    Also, pay attention that the following liquid and solvent may spoil the polarizer:

    *   Water
    *   Ketone
    *   Aromatic Solvents

6) Hold OEL display module very carefully when placing OEL display module into the system housing. Do not apply excessive stress or pressure to OEL display module.   And, do not over bend the film with electrode pattern layouts. These stresses will influence the display performance.   Also, secure sufficient rigidity for the outer cases.

7) Do not apply stress to the driver IC and the surrounding molded sections.

8) Do not disassemble nor modify the OEL display module.

9) Do not apply input signals while the logic power is off.

10) Pay sufficient attention to the working environments when handing OEL display modules to prevent occurrence of element breakage accidents by static electricity.

    *   Be sure to make human body grounding when handling OEL display modules.
    *   Be sure to ground tools to use or assembly such as soldering irons.
    *   To suppress generation of static electricity, avoid carrying out assembly work under dry environments.
    *   Protective film is being applied to the surface of the display panel of the OEL display module.   Be careful since static electricity may be generated when exfoliating the protective film.

11) Protection film is being applied to the surface of the display panel and removes the protection film before assembling it.   At this time, if the OEL display module has been stored for a long period of time, residue

adhesive material of the protection film may remain on the surface of the display panel after removed of the film.   In such case, remove the residue material by the method introduced in the above Section 5).

12)   If electric current is applied when the OEL display module is being dewed or when it is placed under high humidity environments, the electrodes may be corroded and be careful to avoid the above.

14.2   Storage Precautions

1)   When storing OEL display modules, put them in static electricity preventive bags avoiding exposure to direct sun light nor to lights of fluorescent lamps. and, also, avoiding high temperature and high humidity environment or low temperature (less than $0°C$) environments.   (We recommend you to store these modules in the packaged state when they were shipped from Allvision technology Inc.)

At that time, be careful not to let water drops adhere to the packages or bags nor let dewing occur with them.

2)   If electric current is applied when water drops are adhering to the surface of the OEL display module, when the OEL display module is being dewed or when it is placed under high humidity environments, the electrodes may be corroded and be careful about the above.

14.3   Designing Precautions

1)   The absolute maximum ratings are the ratings which cannot be exceeded for OEL display module, and if these values are exceeded, panel damage may be happen.

2)   To prevent occurrence of malfunctioning by noise, pay attention to satisfy the V_{IL} and V_{IH} specifications and, at the same time, to make the signal line cable as short as possible.

3)   We recommend you to install excess current preventive unit (fuses, etc.) to the power circuit (V_{DD}).   (Recommend value: 0.5A)

4)   Pay sufficient attention to avoid occurrence of mutual noise interference with the neighboring devices.

5)   As for EMI, take necessary measures on the equipment side basically.

6)   When fastening the OEL display module, fasten the external plastic housing section.

7)   If power supply to the OEL display module is forcibly shut down by such errors as taking out the main battery while the OEL display panel is in operation, we cannot guarantee the quality of this OEL display module.

8)   The electric potential to be connected to the rear face of the IC chip should be as follows: SSD1315

*   Connection (contact) to any other potential than the above may lead to rupture of the IC.

14.4   Precautions when disposing of the OEL display modules

1)   Request the qualified companies to handle industrial wastes when disposing of the OEL display modules.   Or, when burning them, be sure to observe the environmental and hygienic laws and regulations.

14.5   Other Precautions

1)   When an OEL display module is operated for a long of time with fixed pattern may remain as an after image or slight contrast deviation may occur.

Nonetheless, if the operation is interrupted and left unused for a while, normal state can be restored.   Also, there will be no problem in the reliability of the module.

2)   To protect OEL display modules from performance drops by static electricity rapture, etc., do not touch the following sections whenever possible while handling the OEL display modules.

*   Pins and electrodes

*   Pattern layouts such as the FPC

3)   With this OEL display module, the OEL driver is being exposed.   Generally speaking, semiconductor elements